

## DECISIONS

<b>1. Converting lower ram on BOP to a test ram</b>		
<b>2. Using long string casing instead of liner</b>		
<b>3. Not using the recommended number of centralizers</b>		
<b>4. Not circulating bottoms up prior to cement job</b>		
<b>5. Not waiting for foam stability test</b>		
<b>6. Not running cement bond log</b>		
<b>7. Using spacer made from lost circulation materials (LCM)</b>		