

DECISIONS

1. Converting lower ram on BOP to a test ram		
2. Using long string casing instead of liner		
3. Not using the recommended number of centralizers		
4. Not circulating bottoms up prior to cement job		
5. Not waiting for foam stability test		
6. Not running cement bond log		
7. Using spacer made from lost circulation materials (LCM)		
8. Misinterpreting the Negative Pressure Test		
9. Displacing riser before setting cement plug		
10. Displacing well to over 3,000 ft. below the mud line		
11. Not installing additional physical barriers during temporary abandonment		
12. Performing simultaneous operations during displacement		
13. Not automatically diverting overboard		