

5. Results for the Baseline Case

Top Hat Pressure Probe Reading = 2 psi
Top Hat Internal Temperature = 200F

	Total oil flow BBL/d ¹	Skirt	3 Vents	Riser drill pipe (Measured)	Riser drill pipe (Calculated) ²
LANL	72,700	39,400	18,300	15,000	12,100
LLNL	77,300	42,300	20,000	15,000	14,500
SNL	83,000	45,000	23,000	15,000	15,200

¹Stock Tank Barrels per day

²Calculated riser drill pipe flow provided as a check